

TO BE PUBLISHED ONE TIME ON SEPTEMBER 28, 2011

## SEALED PROPOSALS

Notice is hereby given that bids will be received at the office of the Purchasing Manager, up to 10:00 a.m., Friday, October 28, 2011 for the following project:

**Harry & Woodlawn Intersection  
87N-0494-01/472-84882**

**Lump Sum Bid Items - Paving HSIP Sta 108+50 to 110+50 Harry  
& Sta 51+50 to 54+50 Woodlawn**

Field Office & Laboratory (Type A)	1	LS
Mobilization	1	LS
Mobilization (DBE)	1	LS
Site Clearing	1	LS
Site Restoration	1	LS
Removal of Existing Structure	1	LS
Concr. &/or Asph. Pvm't Rem'd	3,443	sy
Excavation	1,539	cy
Fill, Compacted (95% Density)	72	sy
Concr. Pavement 9" (Reinf.)	2,877	sy
Crushed Rock Base 6", Reinf.	3,100	sy
Concr. C & G, Comb. Type 1	554	lf
Brick Pavers (Concr.), Crosswalk	316	sy
Wheelchair Ramp w/ Detectable Warnings	8	ea

**Lump Sum Bid Items - Traffic HSIP**

Signing, Kansas (TWORKS)	4	ea
Traffic Control	1	LS
Traffic Signalization Harry & Woodlawn	1	LS
Traffic Signalization Temporary	1	LS

**Measured Qty Bid Items - Traffic HSIP**

Signing, Electronic Message Board (each per day)	100	Day
--	-----	-----

**Lump Sum Bid Items - Paving**

Concr. &/or Asph. Sdwlk, Dr, &/or Pkg Lot Rem'd	256	sy
Concr. &/or Asph. Pvm't Rem'd	6,829	sy
Excavation	2,686	cy
Fill, Compacted (95% Density)	133	sy
Concr. Pvm't. 9" (Reinf.)	2,813	sy
Crushed Rock Base 6", Reinf.	3,758	sy
Concr. C & G, Comb. Type 1	954	lf
Concr. C & G, Comb. Type 3 Median	312	lf
Concr. Pvm't. 7" (Reinf)	105	sy
Concr. Pvm't (VG) 8" (Reinf)	111	sy
Crushed Rock Base 7", Reinf.	112	sy
AC Pavement 7" (5" Bit Base)	3,211	sy
Crushed Rock Base 8", Reinf.	3,516	sy

Brick Pavers (Concr.), Median	105	sy
Concr. Ramp Nose Section (Median)	2	ea
Wheelchair Ramp w/ Dectable Warnings	3	ea
Sodding	1	LS
<b>Lump Sum Bid Items - Drainage</b>		
Inlet, Curb (Type 1) (L=15' W=3')	1	ea
Inlet, Curb (Type 1) (L=15' W=5')	2	ea
Inlet Hookups	3	ea
MH, Standard SWS (5')	1	ea
Pipe, RCP 18"	12	lf
Pipe, RCP 36"	195	lf
<b>Lump Sum Bid Items - Traffic</b>		
Pavement Marking	1	LS
Signing	1	LS
<b>Measured Qty Bid Items - Paving</b>		
Concr. Driveway 8" (Reinf.)	11,114	sf
Concr. Sidewalk 4"	2,310	sf
MH Adjusted w/ New Ring & Cover	1	ea
AC Pvmt. 6" (4" Bit Base)	50	sy
AC Pvmt. 6" (4" Bit Base)(Temporary)	100	sy
AC Pvmt., 2" Mill & Overlay (BM-2)(PG70-28)	2,943	sy
Concr. Pvmt. 6" (Reinf.)(Base Repair)	600	sy
Valve Box Adjusted	10	ea
Water Meter Box Adjusted	1	ea
<b>Measured Qty Bid Items - Erosion Control</b>		
BMP, Curb Inlet Protection	3	ea
BMP, Back of Curb Protection	1,600	lf
<b>Non-Participating Bid Items - Paving</b>		
Transportation of Salvage Material	1	LS
<b>Measured Qty Bid Items - Water (Non-participating)</b>		
Fire Hydrant Adjusted	1	ea
Valve Box Adjusted	1	ea
Water Meter Box Adjusted	6	ea

All bids received will thereafter be publicly opened, read aloud and considered by the Board of Bids and Contracts. All work to be done under the direction and supervision of the City Manager and according to plans and specifications on file in the office of the City Engineer. Bidders will be required to enclose a bid bond in the amount of five per cent (5%) with each as a guarantee of good faith. The Wichita City Council reserves the right to reject any and all bids.

Dated at Wichita, Kansas, September 16, 2011.

Karen Sublett, City Clerk

This information and any addenda is also available on the City's Web Page at:  
<http://ep.wichita.gov/>