

TO BE PUBLISHED ONE TIME ON JANUARY 9, 2013

SEALED PROPOSALS

Notice is hereby given that bids will be received at the office of the Purchasing Manager, up to 10:00 a.m., Friday, January 18, 2013 for the following project:

**Floodway Crossing-Phase II, Hoover 9th to 13th
(north of Central, east of Ridge)
472-84817**

Lump Sum Bid Items - Paving (770005)

Mobilization	1	LS
Field Office and Laboratory (Type A)	1	ea
Site Clearing	1	LS
Site Restoration	1	LS
Removal of Existing Structures	1	LS
Transportation of Salvageable Material	1	LS
Pavement &/or Curb Removed	430	sy
Sidewalk, Drive, &/or Parking Lot Removed	417	sy
Fence Removed & Reset	1,233	lf
Excavation	7,659	cy
Fill, Compacted (95% Density)	3,393	cy
Concrete Pavement (VG) 8" Reinf	186	sy
AC Pavement 6" (4" Bit Base)	10,038	sy
Crushed Rock Base 6", Reinforced	11,954	sy
Crushed Rock Base 7", Reinforced	197	sy
Concrete C & G, Type I (6" & 1-1/2")	6,229	lf
Concrete Curb, Mono Edge (6" & 1-1/2")	103	lf
Wheelchair Ramp w/ Detectable Warnings	6	ea

Lump Sum Bid Items - Drainage (770005)

Inlet, Curb (Type 1A) (L=5' W=3')	2	ea
Inlet, Curb (Type 1A) (L=10' W=3')	1	ea
Inlet Hookup	3	ea
Pipe, PVC 4", Perforated (Inlet Underdrain)	53	lf
Pipe, SWS, RCP 12"	112	lf
Pipe, SWS, RCP 15"	76	lf
Pipe, SWS, RCP 18"	196	lf
Pipe, SWS, DIP 18"	84	lf
Pipe, SWS, HERCP (14"x23") {18}	72	lf
Pipe, SWS, HERCP (19"x30") {24}	38	lf
Pipe, SWS, HERCP (24"x38") {30}	108	lf
Pipe, SWS, RCP 15" End Section	5	ea
Pipe, SWS, RCP 18" End Section	7	ea
Pipe, SWS, CMP 18" End Section	2	ea
Pipe, SWS, HERCP 18" End Section	4	ea

Pipe, SWS, HERCP 24" End Section	2	ea
Pipe, SWS, HERCP 30" End Section	4	ea
Fill, Sand (Flushed & Vibrated)	112	lf
Rip-Rap Stone, Slope Protection	30	cy
Concrete Flume	12	ea
Slope Drain (Concrete)	20	lf
Slope Drain (Stone)	216	lf

Lump Sum Bid Items - Traffic (770005)

Signing	1	LS
Traffic Control	1	LS

Lump Sum Bid Items - Landscaping (770005)

Sodding, Bermuda	1	LS
Sodding, Buffalo	1	LS

Measured Quantity Bid Items - Paving (770005)

Concrete Sidewalk 4"	16,381	sf
Concrete Sidewalk 6"	330	sf
Concrete Driveway 8" (Reinf)	7,400	sf
Surfacing Material 6" (SA-1) (Side Street)	1,800	sf
Surfacing Material 2" (SA-1) (Driveway)	60	sf
Retaining Wall	140	sff
Signing, Elec. Portable Message (each per day)	300	Day
Fence Removed	146	lf

Measured Quantity Bid Items - Landscaping (770005)

Small Tree Removal	2	ea
Large Tree Removal	13	ea
Tree, Bur Oak - 2.5" Caliper	13	ea
Tree, Eastern Redcedar - 2.5" Caliper	2	ea

Measured Quantity Bid Items - Erosion Control BMP(770005)

BMP, Curb Inlet Protection	15	ea
BMP, Silt Fence	134	lf
BMP, Construction Entrance	2	ea
BMP, Ditch Check	19	ea
BMP, Back of Curb Protection	806	lf

Water Improvements

Measured Quantity Bid Items (636255)

12" Pipe	426	lf
12" Anc Valve Assembly (Special)	3	ea
Valve Box Adjustment	2	ea
Fire Hydrant Adjustment	1	ea
Fire Hydrant Removal	1	ea
Fire Hydrant Assembly	1	ea
2" Blowoff Assembly	2	ea
Gravel Streets/Roads Removed and Replaced	72	lf
Sand Fill (Flushed and Vibrated)	114	lf
Site Clearing	1	LS
Site Restoration	1	LS

All bids received will thereafter be publicly opened, read aloud and considered by the Board of Bids and Contracts. All work to be done under the direction and supervision of the City Manager and according to plans and specifications on file in the office of the City Engineer. Bidders will be required to enclose a bid bond in the amount of five per cent (5%) with each as a guarantee of good faith. The Wichita City Council reserves the right to reject any and all bids.

Dated at Wichita, Kansas, January 3, 2013.

Karen Sublett, City Clerk

This information and any addenda is also available on the City's Web Page at:
<http://ep.wichita.gov/>