

TO BE PUBLISHED ONE TIME ON SEPTEMBER 14, 2011

SEALED PROPOSALS

Notice is hereby given that bids will be received at the office of the Purchasing Manager, up to 10:00 a.m., Friday, September 23, 2011 for the following project:

**Storm Water Sewer # 661 to serve Monarch Landing 3rd Addition
(north of 21st, west of 159th St. E)
468-84771**

LUMP SUM BID ITEMS

Excavation	11,600	cy
Fill, Compacted (95% Density)	8,900	cy
Fill, Compacted (95% Density) (Contr. Furn.)(On Site)	2,500	cy
Bentonite	6	tn
Bentonite Munipulation	585	sy
Fill, Flowable	115	lf
MH, Standard SWS (4')	1	ea
MH, Shallow SS (4')	6	ea
MH, Shallow SWS (5')	3	ea
Pipe, SWS 12"	1,050	lf
Pipe, SWS 15"	37	lf
Pipe, SWS 18"	142	lf
Pipe, SWS 24"	209	lf
Pipe, SWS 30"	254	lf
Pipe, SWS 42"	106	lf
Inlet, Curb (Type 1A) (L=5' W=3')	1	ea
Inlet, Curb (Type 1A) (L=10' W=3')	4	ea
Inlet, Drop, Special (Area)	1	ea
Rip-Rap, Light Stone	50	sy
Concrete Collar	3	ea
MH Adjusted, SS	1	ea
Trench Drain	1,410	lf
Seeding, Temporary	1	LS
Seeding (Native Prairie Mix)	1	LS
Site Clearing	1	LS
Site Restoration	1	LS

MEASURED QUANTITY BID ITEMS

BMP, Construction Entrance	1	ea
BMP, Curb Inlet Protection	5	ea
BMP, Drop Inlet Protection	12	ea
BMP, Ditch Check	12	ea
BMP, Erosion Control Mat (SC250)	54	sy
BMP, Erosion Control Mat(SC150)	777	sy

All bids received will thereafter be publicly opened, read aloud and considered by the Board of Bids and Contracts. All work to be done under the direction and supervision of the City Manager and according to plans and specifications on file in the office of the City Engineer. Bidders will be required to enclose a bid bond in the amount of five per cent (5%) with each as a guarantee of good faith. The Wichita City Council reserves the right to reject any and all bids.

Dated at Wichita, Kansas, September 7, 2011.

Karen Sublett, City Clerk

This information and any addenda is also available on the City's Web Page at:
<http://ep.wichita.gov/>