

MORE UPCOMING ENGINEERING PROJECTS

General Information

The City of Wichita receives bids at the Purchasing office (455 N.Main, 12th Floor) up to 10:00 a.m. on the Friday this bulletin. All bids received online and/or on paper will thereafter be publicly opened, read aloud, and considered by the Board of Bids and by City Council. The Wichita City Council reserves the right to reject any and all bids.

Plans & Specifications for these projects are generally available 10 days prior to the bid date unless otherwise specified. All work is to be done under direction and supervision of the City Manager and according to the plans & specifications on file in the City Engineer's Office. Bidders are required to include a bid bond in the amount of five percent (5%) with each bid.

Requests for the bid documents & plans should be directed to CBP Reprographics (265-6224). Other questions should be directed to the project Engineer (268-4501).

The successful bidder may contact Kim Pelton (268-4499) for extra sets of plans/specs.

CITY / KDOT PAVING PROJECT to bid October 21, 2011

Seneca, I-235 to 31st Street South

87N-0243-01/472-84006 204358/771634/661688

Bid Date: 10-21-11; Award Date: 10-25-11

Lump Sum Bid Items - Paving (706892)

Site Clearing	1	LS
Site Restoration	1	LS
Mobilization	1	LS
Mobilization (DBE)	1	LS
Field Office & Laboratory (Type A)	1	LS
Removal of Existing Structures	1	LS
Excavation, Common	6,524	cy
Fill, Loose	379	cy
Fill, Compacted (95% Density)	18	cy
Concrete &/or Asphalt Pavement Removed	28,463	sy
Concrete Pavement 9" (NRDJ)	24,926	sy
Concrete Pavement 9" (Reinforced) (AE)	3,117	sy
Concrete Pavement (VG) 8" (Reinf)	1,418	sy
AC Pavement 5" (3" Bit Base)	101	sy
AC Pavement 6" (4" Bit Base)	356	sy
Crushed Rock Base 5", Reinforced	101	sy
Crushed Rock Base 6", Reinforced	31,669	sy
Crushed Rock Base 7", Reinforced	1,655	sy
Concr. C & G, Comb. Type 1 (6" & 1-1/2")	6,774	lf
Concr. C & G, Comb. Type 3 (3-5/8" RL & 1-1/2")	672	lf
Wheelchair Ramp w/ Detectable Warnings	32	ea
Brick Pavers (Concrete), Crosswalk	5,404	sf
Brick Pavers (Concrete), Median	1,153	sf

Lump Sum Bid Items - Drainage (706892)

Inlet, Curb (Type 1A) (L=5' W=4')	37	ea
Inlet, Curb (Type 1A) (L=10' W=4')	4	ea
Inlet, Curb (Type 1) (L=5' W=4')	3	ea
Inlet, Curb (Type 2) (L=3'8" W=3'4 3/8")	11	ea
Inlet, Curb (Type 2) (L=6'2 1/2" W=3'4 3/8")	1	ea
Pipe, RCP 15"	1,590	lf
Pipe, SWS 15"	15	lf
Pipe, RCP 24"	185	lf
Pipe, SWS 24"	14	lf
MH, Standard SWS (4')	1	ea
MH, Reinforced Concrete	19	ea
Fill, Sand (Flushed & Vibrated)	1,774	lf
Inlet Hookup	44	ea

Lump Sum Bid Items - General (706892)

MH Adjusted w/ New Ring & Cover	14	ea
MH Adjusted	1	ea
Valve Box Adjusted	22	ea
Remove and Reconstruct Existing Structures	1	LS
Transportation of Salvaged Material (Non Partic.)	1	LS

(Cont'd)

Page 1 of 2

NOTE: All information contained herein is subject to change.

A minority/women-owned business is 51% owned and controlled by a minority or women. MBE/DBE classes are defined as: Asian (A) American Indian (AI) Black (B) Hispanic (H) and Women-owned (WO). We appreciate your cooperation in providing this information.

MORE UPCOMING ENGINEERING PROJECTS

General Information

The City of Wichita receives bids at the Purchasing office (455 N.Main, 12th Floor) up to 10:00 a.m. on the Friday specified for each project in this bulletin. All bids received online and/or on paper will thereafter be publicly opened, read aloud, and considered by the Board of Bids and by City Council. The Wichita City Council reserves the right to reject any and all bids.

Plans & Specifications for these projects are generally available 10 days prior to the bid date unless otherwise specified. All work is to be done under direction and supervision of the City Manager and according to the plans & specifications on file in the City Engineer's Office. Bidders are required to include a bid bond in the amount of five percent (5%) with each bid.

Requests for the bid documents & plans should be directed to CBP Reprographics (265-6224). Other questions should be directed to the project Engineer (268-4501).

The successful bidder may contact Kim Pelton (268-4499) for extra sets of plans/specs.

Seneca, I-235 to 31st Street South (Cont'd)

Lump Sum Bid Items - Traffic (706892)

Pavement Marking	1	LS
Signing, Street Name Signs Only	1	LS
Traffic Control	1	LS
Traffic Signalization, Temporary (31st & Seneca)	1	LS
Traffic Signalization (34th & Seneca)	1	LS
Traffic Signalization (31st & Seneca)	1	LS

Lump Sum Bid Items - Landscaping (706892)

Sodding	1	LS
---------	---	----

Measured Quantity Bid Items - Paving (706892)

Concrete Driveway 8" (Reinforced) (Class A) (AE)	3,722	sy
Concrete Sidewalk 4"	29,747	sf
Concrete Sidewalk 6"	418	sf
Concrete &/or Asph. Sdwk, Dr, &/or Pkg Lot Rem'd	6,341	sy
Temporary Asphalt Pvmt (6") (SWS Patch)	700	sy
Concrete Sidewalk Protection Curb 8" Max	100	lf
Trees, Large Removed	23	ea
Trees, Small Removed	8	ea
Portable Changeable Electronic Message Sign	60	day
Crushed Rock Hookup 6"	61	sy

Measured Quantity Bid Items - Erosion Control BMP (706892)

BMP, Construction Entrance	4	ea
BMP, Curb Inlet Protection	62	ea
BMP, Back of Curb Protection	4,100	lf

Water Improvements (Non-Participating)

Measured Quantity Bid Items (636247)

Pipe, D1CL 12"	137	lf
Pipe, D1CL 8"	19	lf
Pipe, WL 8"	126	lf
Valve Box Adjusted	2	ea
Fire Hydrant Assembly	6	ea
Fire Hydrant Removal	5	ea
Service Connection Relocated	12	ea
Water Meter Adjusted	17	ea

Sanitary Sewer Improvements (Non-Participating)

Lump Sum Bid Items (620572)

Pipe, SS 8"	138	lf
MH, Standard SS (4')	1	ea
MH Abandoned	2	ea
Pipe Abandoned In Place	165	lf
Pipe Removed (0" - 12")	54	lf
Fill, Flowable	138	lf
Temporary Asphalt Pvmt (6") (SS Patch)	90	sy

NOTE: All information contained herein is subject to change.

A minority/women-owned business is 51% owned and controlled by a minority or women. MBE/DBE classes are defined as: Asian (A) American Indian (AI) Black (B) Hispanic (H) and Women-owned (WO). We appreciate your cooperation in providing this information.