

MORE UPCOMING ENGINEERING PROJECTS

General Information

The City of Wichita receives bids at the Purchasing office (455 N.Main, 12th Floor) up to 10:00 a.m. on the Friday this bulletin. All bids received online and/or on paper will thereafter be publicly opened, read aloud, and considered by the Board of Bids and by City Council. The Wichita City Council reserves the right to reject any and all bids.

Plans & Specifications for these projects are generally available 10 days prior to the bid date unless otherwise specified. All work is to be done under direction and supervision of the City Manager and according to the plans & specifications on file in the City Engineer's Office. Bidders are required to include a bid bond in the amount of five percent (5%) with each bid.

Requests for the bid documents & plans should be directed to City Blue Print Inc. (265-6224). Other questions should be directed to the project Engineer (268-4501).

The successful bidder may contact Kim Pelton (268-4499) for extra sets of plans/specs.

CITY / KDOT PAVING PROJECT to bid JANUARY 13, 2006

21st Street North from Oliver to Woodlawn

87N-0190-01/472-84235 (706923)

Bid Date: 01-13-06; Award Date: 01-24-06

Lump Sum Bid Items

Sawed Joint	8,250	lf
Pvmt Rem	7,443	sy
Sdwk Rem	2,569	sy
Excavation	10,442	cy
Compacted Fill, (95% Density)	1,832	cy
Compacted Fill, (Type B, MR-90)	150	cy
A.C. Pvmt 5" Bituminous Base	2,887	sy
A.C. Pvmt 2" Wearing Surface	22,802	sy
Concr Pvmt, 6"(AE)(Plain)	4,985	sy
2" Milling	15,921	sy
RCVG Pvmt, 7"	1,856	sy
Reinf Crushed Rock Base, 6"	3,140	sy
Reinf Crushed Rock Base, 8"	8,836	sy
Comb C&G	5,676	lf
Wheelchair Ramp	27	ea
Type 1 Curb Inlet, 5' Opening	6	ea
Type 1A Curb Inlet, 5' Opening	1	ea
Type 1A Curb Inlet, 10' Opening	1	ea
Type II Curb Inlet, 2'-3 5/8" Opening	1	ea
Type II Curb Inlet, 4'-10 1/8" Opening	6	ea
Type II Curb Inlet, Special, 4'-10 1/8" Opening	5	ea
MH Stack	1	ea
MH(Type P), 5' Dia.	1	ea
SWS, RCP 15"	320	lf
SWS, RCP 18"	194	lf
SWS, RCP 24"	192	lf
SWS, RCP 36"	43	lf
6' x 4' RCB	1	LS
Flowable Fill (Low Strength)	510	lf
Connection to Existing Structure	10	ea
Conc Collar	1	ea
Valve Box Adjustment	4	ea
MH Adjustment	11	ea
Riprap (Heavy Stone) (D50=18")	62	sy
Site Clearing and Restoration	1	LS
Rem of Existing Structures	1	LS
Field Office and Laboratory (Type A)	1	LS
Mobilization	1	LS
Mobilization (DBE)	1	LS
Erosion Control BMP (Stabilized Entrance)	5	ea
Erosion Control BMP (Curb Inlet Protection)	11	ea
Erosion Control BMP (Back of Curb Protection)	9,475	lf
Erosion Control BMP (Ditch Check)	30	lf
Sodding	7,695	sy
Pvmt Marking	1	LS

Cont'd on Page 2

Page 1 of 2

NOTE: All information contained herein is subject to change.

A minority/women-owned business is 51% owned and controlled by a minority or women. MBE/DBE classes are defined as: Asian (A) American Indian (AI) Black (B) Hispanic (H) and Women-owned (WO). We appreciate your cooperation in providing this information.

MORE UPCOMING ENGINEERING PROJECTS

General Information

The City of Wichita receives bids at the Purchasing office (455 N.Main, 12th Floor) up to 10:00 a.m. on the Friday specified for each project in this bulletin. All bids received online and/or on paper will thereafter be publicly opened, read aloud, and considered by the Board of Bids and by City Council. The Wichita City Council reserves the right to reject any and all bids.

Plans & Specifications for these projects are generally available 10 days prior to the bid date unless otherwise specified. All work is to be done under direction and supervision of the City Manager and according to the plans & specifications on file in the City Engineer's Office. Bidders are required to include a bid bond in the amount of five percent (5%) with each bid.

Requests for the bid documents & plans should be directed to KBP Reprographics (264-9344). Other questions should be directed to the project Engineer (268-4501).

The successful bidder may contact Kim Pelton (268-4499) for extra sets of plans/specs.

21st Street North from Oliver to Woodlawn (Cont'd)

Lump Sum Bid Items

Street Signage	1	LS
Traffic Control	1	LS

Measured Quantity Bid Items

Bit. Base Leveling Course	1,280	ton
Full-Depth Pvmnt Patch	1,256	sy
Driveway Concr Pvmnt, 6"	49	sy
Driveway Concr Pvmnt, 8"	1,240	sy
Sdwlk Concr (4")	28,381	sf
Sdwlk Concr (4")(Special)	243	sf

Non-Participating Items

Street Name Signage	1	LS
Valve Box Adjustment	14	ea
8" Pipe Remove and Replace	376	lf
Rem MH	2	ea
Repl MH Frame & Cover	16	ea
MH Adjustment	10	ea
Install Drop Structure	4	ea
Full-Depth Pvmnt Patch	62	sy
Flowable Fill	115	lf
Transportation of Salvaged Material	1	LS

NOTE: All information contained herein is subject to change.

A minority/women-owned business is 51% owned and controlled by a minority or women. MBE/DBE classes are defined as: Asian (A) American Indian (AI) Black (B) Hispanic (H) and Women-owned (WO). We appreciate your cooperation in providing this information.